

CONTENTS

	PAGE
1 COGENERATION BASICS OF OPERATION	7
1.1 THE CONCEPT OF COGENERATION	7
1.2 COGENERATION PRINCIPLES	8
1.2.1 Heat engines	8
1.2.2 Internal combustion engines	8
1.2.2.1 Otto cycle	9
1.2.2.2 Diesel cycle	9
1.2.3 Gas turbines	9
1.2.3.1 The Brayton (or Joule) cycle	9
1.2.4 Steam turbines	10
1.2.4.1 The Rankine cycle	11
1.2.5 Combustion principles	11
1.2.5.1 Fuel types	11
1.2.5.2 Heating values of fuels	12
1.2.5.3 Combustion emissions	12
1.2.6 Performance indices of cogeneration systems	13
1.3 CLASSIFICATION OF COGENERATION SYSTEMS	14
1.3.1 Types of Cogeneration Concepts	14
1.3.2 Operation modes of cogeneration systems	15
2 CHP SYSTEM MAIN COMPONENTS	16
2.1 PRIME MOVER OPTIONS	16
2.1.1 Introduction	16
2.1.2 Reciprocating Engines	16
2.1.3 Gas turbines	17
2.1.4 Steam Turbines	18
2.1.5 Micro-turbines	19
2.1.6 Fuel cells	20
2.1.7 Technology summary	20
2.2 ELECTRIC POWER GENERATORS	20
2.2.1 Principles of electrical machines	21
2.2.2 Synchronous machines	22
2.2.3 Asynchronous (induction) machines	23
2.2.4 Generator selection	23
2.3 HEAT RECOVERY	24
2.3.1 Heat recovery options	24
2.3.2 Heat recovery boilers	24
2.3.3 Heat recovery in reciprocating engines	25
2.3.4 Heat recovery in steam turbines	26
2.3.5 Gas turbine heat recovery	26
2.3.6 Heat recovery in micro-turbines and fuel cells	26
2.4 CONTROL AND MONITORING SYSTEMS	27
2.4.1 Control systems	27
2.4.2 Long-term performance monitoring	28
3 AUXILIARIES, INTERCONNECTIONS & INTERFACES	28
3.1 HEAT RECOVERY AND DISTRIBUTION DEVICES	28
3.1.1 Heat recovery boilers and the exhaust system	28
3.1.2 Supplementary and auxiliary firing	29
3.1.3 Heat output from the CHP package	29
3.1.4 Distribution of heat	30
3.1.4.1 Valves and fluid-handling devices	31
3.1.4.2 Steam-lines considerations	32
3.2 FUEL SUPPLY SYSTEMS	33
3.2.1 Natural gas supplies	33
3.2.2 Coal, oil and other fuels supplies	34
3.3 ELECTRICAL SUPPLY SYSTEMS	34
3.3.1 Utility interconnections	34
3.3.2 Voltage regulation	35
3.3.3 Fault control	36

3.3.4	Protection	36
3.4	OTHER TECHNOLOGICAL ISSUES OF CONCERN	37
3.4.1	Trigeneration and absorption cooling	37
3.4.1.1	<i>The concept of Trigeneration</i>	37
3.4.1.2	<i>Chillers</i>	38
3.4.2	Silencers	39
3.4.2.1	<i>Acoustic housings and enclosures</i>	39
3.4.2.2	<i>Other ways of noise attenuation</i>	39
4	COGENERATION APPLICATIONS	39
4.1	INTRODUCTION	39
4.2	TERTIARY SECTOR	40
4.2.1	Background	40
4.2.2	Case study - Jurys Hotel and Towers -DUBLIN	41
4.2.3	Outlook	41
4.3	INDUSTRY	41
4.3.1	Background	41
4.3.2	Case study -Buchanan Flooring	42
4.3.2.1	<i>Electricity uses</i>	42
4.3.2.2	<i>Plant overview</i>	42
4.3.3	Outlook	43
4.4	DISTRICT HEATING/COOLING	43
4.4.1	Background	43
4.4.2	System considerations	44
4.4.3	Thermal energy generation	44
4.4.4	Case study -Lutherstadt Wittenberg	44
4.4.5	Case study -District heating of Cham (Switzerland)	45
4.4.5.1	<i>The principle of operation</i>	45
4.4.5.2	<i>Economics</i>	46
4.5	APPLICATIONS ACCORDING TO THE PRIME MOVERS	46
4.5.1	Application of reciprocating engines	46
4.5.2	Application of steam turbines	47
4.5.3	Application of gas turbines	47
4.5.4	Application of fuel cells	47
5	CHP SYSTEM SELECTION	47
5.1	INITIAL CONSIDERATIONS	47
5.1.1	Introduction	47
5.1.2	Considerations for CHP project development	48
5.2	PROCEDURE FOR SYSTEM SELECTION AND DESIGN	48
5.2.1	Background	48
5.2.2	Preliminary assessment	49
5.2.3	Feasibility study and system selection	50
5.2.4	Identifying a CHP plant of an appropriate output	51
5.2.5	Detailed design	51
5.3	ASSESSMENT OF IMPORTANT TECHNICAL PARAMETERS	52
5.3.1	Site energy demands	52
5.3.1.1	<i>Future energy demands</i>	52
5.3.1.2	<i>Timing of demands</i>	53
5.3.2	Factors affecting the selection of the suitable CHP plant	53
5.3.2.1	<i>Heat to power ratio</i>	53
5.3.2.2	<i>Quality of thermal energy needed</i>	53
5.3.2.3	<i>Fuel supply</i>	54
5.3.2.4	<i>Noise levels</i>	54
5.3.2.5	<i>Other issues of concern</i>	54
5.3.2.6	<i>Regulatory and local planning issues</i>	55
5.3.3	Practical aspects of installing a CHP plant	55
5.4	FINANCIAL ASSESSMENT OF A CHP PROJECT	55
5.4.1	Key parameters for the economic analysis	55
5.4.2	Tools for the financial analysis of CHP projects	56
5.4.3	Assessment of financial feasibility of CHP projects	57
5.4.4	Sensitivity analysis	58

6	LEGAL STATUS & FINANCING OPPORTUNITIES	59
6.1	LEGAL AND INSTITUTIONAL FRAMEWORK CONDITIONS	59
6.1.1	Background	59
6.1.2	European Union law	59
6.1.2.1	<i>Communication from the Commission to the Council and the European Parliament: "A Community strategy to promote combined heat and power and to dismantle barriers to its development" (15.10.97)</i>	59
6.1.2.2	<i>European Union programmes supporting CHP</i>	59
6.1.2.3	<i>Internalisation of external costs</i>	60
6.1.2.4	<i>Action plan to improve energy efficiency in the European Community</i>	60
6.1.2.5	<i>Directive concerning the common rules for the internal market in electricity</i>	62
6.1.2.6	<i>EU Directive on the promotion of electricity from RES in the internal market</i>	62
6.1.3	The situation in Germany	62
6.1.3.1	<i>Law for the protection of the production of electricity produced from combined heat and power plants</i>	62
6.1.3.2	<i>The ecological tax reform</i>	62
6.1.3.3	<i>Renewable Energy Law</i>	63
6.1.4	The situation in Greece	63
6.1.4.1	<i>Overview</i>	63
6.1.4.2	<i>The Operational Programme for Energy (OPE)</i>	64
6.1.4.3	<i>Other relevant laws</i>	64
6.1.5	The situation in other EU countries	65
6.2	FINANCIAL INSTRUMENTS	67
6.2.1	Financing problems	67
6.2.2	On-balance-sheet financing options	68
6.2.2.1	<i>Internal funding</i>	68
6.2.2.2	<i>Debt finance</i>	68
6.2.2.3	<i>Leasing</i>	68
6.2.3	Off-balance-sheet financing options	69
6.2.3.1	<i>Equipment supplier finance</i>	69
6.2.3.2	<i>ESCO contracts</i>	69
6.2.4	Making the choice between options	70
6.2.5	Joint Ventures	70
7	CHP SYSTEM INTEGRATION AND COMMISSIONING	70
7.1	PROJECT IMPLEMENTATION	70
7.1.1	Possible implementation routes	70
7.1.1.1	<i>In-house resources</i>	70
7.1.1.2	<i>Turnkey procedure</i>	70
7.1.1.3	<i>Integrated energy services procedure</i>	71
7.1.2	Specification of requirements	71
7.1.3	The tender and design procedure	71
7.1.3.1	<i>In-house resources projects</i>	71
7.1.3.2	<i>Turnkey projects</i>	72
7.1.3.3	<i>Energy services contract projects</i>	72
7.1.4	Project risks and project management	73
7.2	CONTRACTUAL TERMS, RESPONSIBILITIES AND LIABILITY	74
7.2.1	Background	74
7.2.2	Design and construction contract	75
7.2.3	Operation and maintenance contracts	76
7.2.4	Off-take contracts	77
7.3	INSTALLATION OF A CHP SYSTEM	78
7.3.1	Managing the installation	78
7.3.1.1	<i>In-house resources project</i>	78
7.3.1.2	<i>Turnkey project</i>	78
7.3.1.3	<i>Energy services contract project</i>	78
7.3.2	Minimising the disruption	78
7.3.3	Varying the specification	79
7.4	COMMISSIONING AND TESTING PROCEDURE	79
7.4.1	Background	79
7.4.2	Types of tests	79
7.4.3	Specific aspects of CHP project testing	80

8	CHP SYSTEM OPERATION & MAINTENANCE	80
8.1	INTRODUCTION	80
8.2	CHP PLANT OPERATION	81
8.2.1	Basics of operation	81
8.2.2	CHP plant control strategy	81
8.2.2.1	<i>Control systems associated with individual plant items</i>	81
8.2.2.2	<i>Monitoring and advisory systems</i>	82
8.2.2.3	<i>Distributed systems for total plant control</i>	82
8.2.2.4	<i>Manual control of individual plant systems</i>	83
8.2.3	Planning and managing plant shutdowns	83
8.2.4	Staff training	83
8.2.5	Safety issues relating to plant operation	83
8.3	CHP PLANT MAINTENANCE	83
8.3.1	Maintenance options	83
8.3.2	Maintenance contracts for CHP plant	84
8.3.3	Maintenance requirements for CHP prime movers/electrical generators	85
8.3.3.1	<i>Gas turbines</i>	85
8.3.3.2	<i>Reciprocating engines</i>	85
8.3.3.3	<i>Steam turbines</i>	86
8.3.3.4	<i>Micro-turbines</i>	86
8.3.3.5	<i>Fuel cells</i>	86
8.3.4	Maintenance requirements for site systems	86
8.4	CHP PLANT PERFORMANCE MANAGEMENT	87
8.4.1	Importance of the efficient system management	87
8.4.2	Plant condition monitoring	88
8.4.3	Auditing CHP plant performance	88
8.4.4	Plant performance monitoring	88
APPENDIX		91
REFERENCES		93